




# HECO-UNIX-plus HECO-UNIX-top

# **European Technical Assessment ETA-11/0452**

HECO-UNIX-plus and HECO-UNIX-top screws Self-tapping screws for use in timber constructions







Approval body for construction products and types of construction

**Bautechnisches Prüfamt** 

An institution established by the Federal and Laender Governments



### European Technical Assessment

ETA-11/0452 of 23 May 2016

English translation prepared by DIBt - Original version in German language

#### **General Part**

Technical Assessment Body issuing the European Technical Assessment:

Trade name of the construction product

Product family to which the construction product belongs

Manufacturer

Manufacturing plant

This European Technical Assessment contains

This European Technical Assessment is issued in accordance with Regulation (EU) No 305/2011, on the basis of

This version replaces

Deutsches Institut für Bautechnik

HECO-UNIX-plus and HECO-UNIX-top screws

Self-tapping screws for use in timber constructions

HECO-Schrauben GmbH & Co. KG Dr.-Kurt-Steim-Straße 28 78713 Schramberg DEUTSCHLAND

HECO-Schrauben GmbH & Co. KG Dr. Kurt-Steim-Straße 28 78713 Schramberg

19 pages including 3 annexes which form an integral part of this assessment

European Assessment Document (EAD) 130118-00-0603

ETA-11/0452 issued on 6 December 2011



#### European Technical Assessment ETA-11/0452 English translation prepared by DIBt

original issued document and shall be identified as such.

Page 2 of 19 | 23 May 2016

The European Technical Assessment is issued by the Technical Assessment Body in its official language. Translations of this European Technical Assessment in other languages shall fully correspond to the

Communication of this European Technical Assessment, including transmission by electronic means, shall be in full. However, partial reproduction may only be made with the written consent of the issuing Technical Assessment Body. Any partial reproduction shall be identified as such.

This European Technical Assessment may be withdrawn by the issuing Technical Assessment Body, in particular pursuant to information by the Commission in accordance with Article 25(3) of Regulation (EU) No 305/2011.



#### European Technical Assessment ETA-11/0452 English translation prepared by DIBt

Page 3 of 19 | 23 May 2016

#### Specific part

#### 1 Technical description of the product

HECO-UNIX-plus and HECO-UNIX-top screws are screws made from special carbon steel or stainless steel. Screws made from carbon steel are hardened. They have a corrosion protection according to Annex A.2.6. The outer thread diameter is not less than 3.5 mm and not greater than 6.0 mm. The overall length of the screws is ranging from 16 mm to 300 mm. Further dimensions are shown in Annex 3.

#### 2 Specification of the intended use in accordance with the applicable European Assessment Document

The performances given in Section 3 are only valid if the HECO-UNIX-plus and HECO-UNIX-top screws are used in compliance with the specifications and conditions given in Annex 1 and 2.

Durability is only ensured if the specifications of intended use according to Annex 1 and 2 are taken into account.

The verifications and assessment methods on which this European Technical Assessment is based lead to the assumption of a working life of the HECO-UNIX-plus and HECO-UNIX-top screws of at least 50 years. The indications given on the working life cannot be interpreted as a guarantee given by the producer, but are to be regarded only as a means for choosing the right products in relation to the expected economically reasonable working life of the works.

#### 3 Performance of the product and references to the methods used for its assessment

#### 3.1 Mechanical resistance and stability (BWR 1)

Essential characteristic	Performance
Dimensions	See Annex 3
Characteristic yield moment	See Annex 2
Characteristic withdrawal parameter	See Annex 2
Characteristic head pull-through parameter	See Annex 2
Characteristic tensile strength	See Annex 2
Characteristic yield strength	No performance determined
Characteristic torsional strength	See Annex 2
Insertion moment	See Annex 2
Spacing, end and edge distances of the screws and minimum thickness of the wood based material	See Annex 2
Slip modulus for mainly axially loaded screws	See Annex 2



## European Technical Assessment ETA-11/0452

Page 4 of 19 | 23 May 2016

English translation prepared by DIBt

#### 3.2 Safety in case of fire (BWR 2)

Essential characteristic	Performance
Reaction to fire	The screws are made of steel classified as Euroclass A1 in accordance with EC decision 96/603/EC, as amended by EC decision 2000/605/EC.

#### 3.3 Hygiene, health and the environment (BWR 3)

Essential characteristic	Performance	
Content, emission and/or release of dangerous substances	The product does not contain cadmium.	

3.4 Safety and accessibility in use (BWR 4)

Same as BWR 1

3.5 Protection against noise (BWR 5)

Not applicable

3.6 Energy economy and heat retention (BWR 6)

Not applicable

3.7 Sustainable use of natural resources (BWR 7)

For the sustainable use of natural resources no performance was investigated for this product.

4 Assessment and verification of constancy of performance (AVCP) system applied, with reference to its legal base

In accordance with EAD No. 130118-00-0603, the applicable European legal act is: 97/176/EC. The system to be applied is: 3

5 Technical details necessary for the implementation of the AVCP system, as provided for in the applicable EAD

Technical details necessary for the implementation of the AVCP system are laid down in the control plan deposited with Deutsches Institut für Bautechnik.

Issued in Berlin on 23 May 2016 by Deutsches Institut für Bautechnik

Andreas Kummerow beglaubigt:
Head of Department Dewitt



#### Annex 1 Specifications of intended use

#### A.1.1 Use of the HECO-UNIX-plus and HECO-UNIX-top screws only for:

Static and quasi-static loads

#### A.1.2 Base materials

The self-tapping screws are used for connections in load bearing timber structures between wood-based members or between those members and steel members:

- Solid timber (softwood) according to EN 14081-1<sup>1</sup>,
- Glued laminated timber (softwood) according to EN 14080<sup>2</sup>,
- Laminated veneer lumber LVL (softwood) according to EN 14374³, arrangement of the screws only at an angle  $\alpha$  of 60° ≤  $\alpha$  ≤ 90° to the plane of the veneers, where  $\alpha$  is the angle between screw axis and the plane of the veneer,
- Glued solid timber (softwood) according to EN 14080 or national provisions that apply at the installation site,
- Cross-laminated timber (softwood) according to European Technical Approvals/ Assessments or national provisions that apply at the installation site.

The screws may be used for connecting the following wood-based panels to the timber members mentioned above:

- Plywood according to EN 636<sup>4</sup> and EN 13986<sup>5</sup>,
- Oriented Strand Board, OSB according to EN 300<sup>6</sup> and EN 13986,
- Particleboard according to EN 312<sup>7</sup> and EN 13986,
- Fibreboards according to EN 622-2<sup>8</sup>, EN 622-3<sup>9</sup> and EN 13986.
- Cement-bonded particle boards according to EN 634-2<sup>10</sup> and EN 13986,
- Solid-wood panels according to EN 13353<sup>11</sup> and EN 13986.

Wood-based panels shall only be arranged on the side of the screw head.

1	EN 14081-1:2005+A1:2011	Timber structures – Strength graded structural timber with rectangular cross section – Part 1:
2	EN 14080:2013 EN 14374:2004	General requirements Timber structures - Glued laminated timber and glued solid timber - Requirements Timber structures - Structural laminated veneer lumber - Requirements
4	EN 636:2012+A1:2015	Plywood - Specifications
5	EN 13986:2004+A1:2015	Wood-based panels for use in construction - Characteristics, evaluation of conformity and marking
6	EN 300:2006	Oriented strand boards (OSB) - Definition, classification and specifications
7	EN 312:2010	Particleboards - Specifications
8	EN 622-2:2004	Fibreboards – Specifications – Part 2: Requirements for hardboards
9	EN 622-3:2004	Fibreboards - Specifications - Part 3: Requirements for medium boards
10	EN 634-2:2007	Cement-bonded particleboards – Specifications – Part 2: Requirements for OPC bonded particleboards for use in dry, humid and external conditions
11	EN 13353:2011+A1:2011	Solid wood panels (SWP) – Requirements

HECO-UNIX-plus and HECO-UNIX-top screws

Specifications of intended use

Annex 1



#### A.1.3 Use Conditions (environmental conditions)

The corrosion protection of the HECO-UNIX-plus and HECO-UNIX-top screws is specified in Annex A.2.6. With regards to the use and the environmental conditions, the national provisions of the place of installation apply.

#### A.1.4 Installation provisions

EN 1995-1-1<sup>12</sup> in conjunction with the respective National Annex applies for the installation.

The screws are either driven into the wood-based member made of softwood without pre-drilling or in pre-drilled holes with a diameter according to Table A.1.

Table A.1 Diameter of the pre-drilled holes in softwood

Outer thread diameter d [mm]	Diameter of the pre-drilled hole with a tolerance of ± 0.1 mm
[,,,,,]	[mm]
	Softwood
3,5	2,0
4,0	2,5
4,5	3,0
5,0	3,0
6,0	4,0

The screw holes in steel members shall be pre-drilled with an adequate diameter greater than the outer thread diameter.

A minimum of two screws shall be used for connections in load bearing timber structures. This does not apply for special situations specified in National Annexes to EN 1995-1-1.

Only one screw may be used in structural connections when the minimum penetration length of the screw is  $20 \cdot d$ , the screw is only axially loaded and the angle between screw axis and grain direction is  $\alpha \ge 15^{\circ}$ . The load-bearing capacity of the screw shall be reduced by 50 %. If the screw is used as tensile reinforcement of timber structures perpendicular to the grain no reduction of the load-bearing capacity of the screw is required.

By fastening screws in wood-based members the head of the screws shall be flush with the surface of the wood-based member. For raised countersunk, cylinder and pan head the head part k respectively f remains unconsidered.

EN 1995-1-1:2004+A1:2008+A2:2014 Eurocode 5: Design of timber structures – Part 1-1: General - Common rules and rules for buildings

HECO-UNIX-plus and HECO-UNIX-top screws	
Installation provisions	Annex 1



#### ANNEX 2 - Characteristic values of the load-carrying capacities

Table A.2.1 Characteristic load-carrying capacities of HECO-UNIX-plus and HECO-UNIX-top screws

Outer thread diameter [mm]		3.5	4.0	4.5	5.0	6.0
Characteristic yield	Carbon steel	2.3	2.8	4.5	5.9	9.5
moment M <sub>y,k</sub> [Nm]	Stainless steel	-	1	3.7	4.9	-
Characteristic tensile strength f <sub>tens,k</sub> [kN]	Carbon steel	3.4	4.4	5.6	7.9	11.3
	Stainless steel	-	-	5.3	7.4	-
Characteristic torsional strength f <sub>tor,k</sub> [Nm]	Carbon steel	2.1	2.9	4.5	6.2	11.0
	Stainless steel	-	-	4.1	6.0	-

#### A.2.1 General

The minimum penetration length of the threaded part of the screw lef shall be

$$I_{ef} = min\begin{cases} \frac{4 \cdot d}{\sin \alpha} \\ 20 \cdot d \end{cases}$$

#### where

 $\alpha$  angle between screw axis and grain direction

d outer thread diameter of the screw.

The outer thread diameter of screws inserted in cross-laminated timber shall be at least 6 mm. To connect cross-laminated timber the inner thread diameter  $d_1$  of the screws shall be greater than the maximal width of the gaps in the layer.

#### A.2.2 Laterally loaded screws

#### A.2.2.1 General

The outer thread diameter d shall be used as effective diameter of the screw according to EN 1995-1-1.

The embedding strength for the screws in wood-based members or in wood-based panels shall be taken from EN 1995-1-1 or from national provisions that apply at the installation site unless otherwise specified in the following.

HECO-UNIX-plus and HECO-UNIX-top screws	
Characteristic values of the load-carrying capacities	Annex 2



#### A.2.2.2 Solid timber, glued laminated timber and glued solid timber

The embedding strength for screws in non-pre-drilled holes in softwood arranged at an angle between screw axis and grain direction of  $0^{\circ} \le \alpha \le 90^{\circ}$  is:

$$f_{h,k} = \frac{0.082 \cdot \rho_k \cdot d^{-0.3}}{2.5 \cdot \cos^2 \alpha + \sin^2 \alpha}$$
 (2.1)

The embedding strength for screws in pre-drilled holes in softwood arranged at an angle between screw axis and grain direction of  $0^{\circ} \le \alpha \le 90^{\circ}$  is:

$$f_{h,k} = \frac{0.082 \cdot \rho_k \cdot (1 - 0.01 \cdot d)}{2.5 \cdot \cos^2 \alpha + \sin^2 \alpha}$$
 (2.2)

where

 $\rho_k$  Characteristic density of the wood-based member, for LVL  $\rho_k \le 500 \text{ kg/m}^3$ 

d Outer thread diameter of the screw [mm]

 $\alpha$  Angle between screw axis and grain direction,  $0^{\circ} \le \alpha \le 90^{\circ}$ .

#### A.2.2.3 Cross laminated timber

The embedding strength for screws arranged in the edge surfaces parallel to the plane of cross laminated timber may be assumed according to equation (2.3) independent of the angle between screw axis and grain direction,  $0^{\circ} \le \alpha \le 90^{\circ}$ :

$$f_{hk} = 20 \cdot d^{-0.5} \text{ in N/mm}^2$$
 (2.3)

unless otherwise specified in the technical specification of the cross laminated timber.

Where d is the outer thread diameter of the screws in mm.

Equation (2.3) is only valid for softwood layers. The provisions in the European Technical Approval/ Assessment or in national provisions of the cross laminated timber apply.

The embedding strength for screws in the wide face of cross laminated timber should be assumed as for solid timber based on the characteristic density of the outer layer. Where applicable, the angle between force and grain direction of the outer layer shall be taken into account. The direction of the lateral force shall be perpendicular to the screw axis and parallel to the wide face of the cross laminated timber.

#### A.2.3 Axially loaded screws

The axial slip modulus  $K_{ser}$  of the threaded part of a screw for the serviceability limit state per side shall be taken independent of angle  $\alpha$  to the grain as:

$$K_{ser} = 780 \cdot d^{0.2} \cdot l_{ef}^{0.4}$$
 [N/mm] (2.4)

where

d outer thread diameter of the screw [mm]

lef penetration length of the of the threaded part of the screw in the wood-based member [mm].

HECO-UNIX-plus and HECO-UNIX-top screws	_
Characteristic load-bearing capacity values	Annex 2



#### A.2.3.1 Axial withdrawal capacity

The characteristic withdrawal capacity in solid timber, glued laminated timber, cross laminated timber or laminated veneer lumber members made from softwood at an angle of  $0^{\circ} \le \alpha \le 90^{\circ}$  to the grain shall be calculated as:

$$F_{ax,\alpha,Rk} = n_{ef} \cdot k_{ax} \cdot f_{ax,k} \cdot d \cdot \ell_{ef} \cdot \left(\frac{\rho_k}{350}\right)^{0.8}$$
 (2.5)

where

 $F_{ax,\alpha,Rk}$  Characteristic withdrawal capacity of a screw group at an angle  $\alpha$  to the grain [N]

n<sub>ef</sub> Effective number of screws according to EN 1995-1-1:2008, clause 8.7.2 (8)

For inclined screws with an angle between shear plane and screw axis  $30^{\circ} \le \alpha \le 60^{\circ}$ :

$$n_{ef} = \max \left\{ n^{0.9}; 0.9 \cdot n \right\}$$
 (2.6)

For inclined screws as fasteners in mechanically jointed beams or columns or for the fixing of thermal insulation material,  $n_{ef} = n$ .

n Number of screws acting together in a connection. If crossed pairs of screws are used in timber-to-timber connections, n is the number of crossed pairs of screws.

 $\textbf{k}_{\text{ax}}$  Factor, taking into account the angle  $\alpha$  between screw axis and grain direction

$$k_{ax} = 1.0$$
 for  $45^{\circ} \le \alpha \le 90^{\circ}$ 

$$k_{ax} = 0.3 + \frac{0.7 \cdot \alpha}{45^{\circ}}$$
 for  $15^{\circ} \le \alpha < 45^{\circ}$  (2.7)

Equation (2.7) may be used for angles  $\alpha$  between screw axis and grain direction  $0^{\circ} \le \alpha < 15^{\circ}$  if the following requirements are fulfilled:

- 1. The screws are inserted in solid timber, glued laminated timber, glued solid timber or laminated veneer lumber made from softwood.
- 2. The penetration length of the threaded part of the screws is

$$I_{\text{ef,req}} = \min \begin{cases} \frac{4 \cdot d}{\sin \alpha} \\ 20 \cdot d \end{cases}$$

3. At least four screws are used in a connection.

 $f_{ax,k}$  Characteristic withdrawal parameter at an angle  $\alpha$  = 90° based on a characteristic density of the wood-based member  $\rho_k$  of 350 kg/m³

 $f_{ax,k} = 11.8 \text{ N/mm}^2$ .

The characteristic withdrawal parameter is also valid for softwood layers of cross-laminated timber.

 $\rho_k$  Characteristic density of the wood-based member, for LVL  $\rho_k \le 500 \text{ kg/m}^3$ 

For screws penetrating more than one layer of cross-laminated timber the different layers may be taken into account proportionally. In the lateral surfaces of the cross-laminated timber the screws shall be fully inserted in one layer.

HECO-UNIX-plus and HECO-UNIX-top screws	
Characteristic load-bearing capacity values	Annex 2



#### A.2.3.2 Head pull-through capacity

The characteristic head pull-through capacity in solid timber, glued laminated timber, cross laminated timber, laminated veneer lumber members and wood-based panels shall be calculated as:

$$F_{ax,\alpha,Rk} = n_{ef} \cdot f_{head,k} \cdot d_h^2 \cdot \left(\frac{\rho_k}{350}\right)^{0.8} [N]$$
 (2.8)

where:

 $F_{ax,\alpha,RK}$  Characteristic head pull-through capacity of the connection at an angle  $\alpha \ge 30^{\circ}$  to the grain [N]

n<sub>ef</sub> Effective number of screws according to EN 1995-1-1:2008, clause 8.7.2 (8)

For inclined screws with an angle between shear plane and screw axis 30° ≤ α ≤ 60°:

$$n_{ef} = max \left\{ n^{0.9}; 0.9 \cdot n \right\}$$

For inclined screws as fasteners in mechanically jointed beams or columns or for the fixing of thermal insulation material,  $n_{\rm ef}$  = n.

n Number of screws acting together in a connection. If crossed pairs of screws are used in timber-to-timber connections, n is the number of crossed pairs of screws.

f<sub>head.k</sub> Characteristic head pull-through parameter of the screw [N/mm²]

d<sub>h</sub> Diameter of the screw head [mm]

Characteristic density of the wood-based member or of the wood-based panel [kg/m³], for wood-based panels  $\rho_k \le 380 \text{ kg/m}^3$ , for LVL  $\rho_k \le 500 \text{ kg/m}^3$ 

Characteristic head pull-through parameter for HECO-UNIX-plus and HECO-UNIX-top screws in connections with softwood timber for a characteristic density of 350 kg/m³ of the timber and for wood-based panels like

- Plywood according to EN 636 and EN 13986
- Oriented strand board, OSB according to EN 300 and EN 13986
- Particleboard according to EN 312 and EN 13986
- Fibreboards according to EN 622-2, EN 622-3 and EN 13986
- Cement-bonded particle boards according to EN 634-2 and EN 13986,
- Solid-wood panels according to EN 13353 and EN 13986.

with a thickness of more than 20 mm is

 $f_{head,k} = 13.0 \text{ N/mm}^2$ .

For wood based panels with a thickness 12 mm  $\leq$  t  $\leq$  20 mm the characteristic value of the head pull-through parameter for HECO-UNIX-plus and HECO-UNIX-top screws is:

 $f_{head k} = 8.0 \text{ N/mm}^2$ 

For wood based panels with a thickness of less than 12 mm the characteristic head pull-through capacity for the screws shall be based on a characteristic value of the head pull-through parameter of 8 N/mm², and limited to 400 N complying with the minimum thickness of the wood based panels of 1.2·d, with d as outer thread diameter and the values in Table A.2.2.






Table A.2.2 Minimum thickness of wood based panels

Wood based panel	Minimum thickness [mm]
Plywood	6
Fibreboards (hardboards and medium boards)	6
Oriented Strand Boards, OSB	8
Particleboards	8
Cement-bonded particle board	8
Solid wood Panels	12

For HECO-UNIX-plus and HECO-UNIX-top screws with a full thread the withdrawal capacity of the thread in the wood-based member with the screw head may be taken into account instead of the head pull-through capacity. The minimum penetration length of the thread of  $4 \cdot d$  shall be considered in the timber member near the screw head.

In steel-to-timber connections the head pull-through capacity is not governing.

#### A.2.4 Spacing, end and edge distances of the screws and minimum thickness of the wood based material

Minimum thickness for structural wood-based members made from solid timber, glued laminated timber, glued solid timber, laminated veneer lumber and cross-laminated timber is t = 24 mm.

#### A.2.4.1 Laterally and/or axially loaded screws

Screws in pre-drilled holes

For HECO screws in pre-drilled holes the minimum spacing, end and edge distances are given in EN 1995-1-1:2004+A1: 2008, clause 8.3.1.2 and Table 8.2 as for nails in pre-drilled holes. Here, the outer thread diameter d shall be considered.

Screws in non pre-drilled holes

For HECO screws in non pre-drilled holes minimum spacing and distances are given in EN 1995-1-1:2004+A1: 2008, clause 8.3.1.2 and Table 8.2 as for nails in non-predrilled holes. Here, the outer thread diameter d shall be considered.

For Douglas fir members minimum spacing and distances parallel to the grain shall be increased by 50%.

Minimum distances from the unloaded edge perpendicular to the grain may be reduced to  $3 \cdot d$  also for timber thickness  $t < 5 \cdot d$ , if the spacing parallel to the grain and the end distance is at least  $25 \cdot d$ .

#### A.2.4.2 Only axially loaded screws

For HECO-UNIX-plus and HECO-UNIX-top screws the minimum spacing, end and edge distances are given in EN 1995-1-1:2004+A1: 2008, clause 8.7.2 and Table 8.6.

#### A.2.5 Insertion moment

The ratio between the characteristic torsional strength  $f_{tor,k}$  and the mean value of insertion moment  $R_{tor,mean}$  fulfills the requirement for all screws.

nnex 2



#### A.2.6 Durability against corrosion


Screws made from carbon steel may have the coatings according to Table A.2.3

Table A.2.3 Coatings of the screws

Coating		Thickness of the coating [μm]					
electrogalvanised	blue chromated						
	yellow chromated	4 - 10					
	black chromated	4 - 10					
	olive chromated						
zinc-nickel coating, galva	nic cladded, chromated	8 - 12					
zinc flake basecoat		12 - 18					

Steel no. 1.4567 is used for screws made from stainless steel. Contact corrosion shall be avoided.


HECO-UNIX-plus and HECO-UNIX-top screws	
Durability against corrosion	Annex 2



Nom.	Diameter	Ø	3,5	Ø	4,0	Ø	4,5	Ø	5,0	Ø					
d upper tol. lower tol.		3,5	+0,3 -0,1	4,0	+0,3 -0,1	4,5	+0,3 -0,1	5,0	+0,3 -0,1	6,0	+0,3 -0,1				
<i>d</i> 1	1 upper tol. 2,35 2,6 lower tol. 2,15 2,4		2 2	2,9 2,7		3,2 3,0		4,15 3,8							
<i>d</i> h	upper tol. lower tol.	6,9	+0,1 -0,4	7,9	+0,1 -0,4	8,9	+0,1 -0,4	9,6	+0,1 -0,4	11,7	7 <sup>+0,1</sup> <sub>-0,4</sub>				
ds	upper tol. lower tol.									4,4	45 ,2				
P			Variable thread pitch												
k	upper tol. lower tol.		,1 ,8		,5 ,1		,7 ,3		,0 ,6		,6 ,1				
Re	ecess Z	2	2		2	2	2	2		3	3				
t	t upper tol. 2,15 lower tol. 1,7				2,6 2,05		3,15 2,65		3,6 3,0		3,6 3,0				
	m	4	,0	4,4		4,9		5,3		6,6					
	L	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt
	20	16													
	25	21		21		21		20							
	30	26		26		26		25		24					
	35 40	31 36		31 36		31 36		30 35		29 34					
	45	41		41		41		40		39					
	50	46		41		46		45		44					
	55	40		51		51		50		49					
	60			56		56		55		54					$\vdash$
	65			61		61		60		59					
	70			66		66		65		64					
	75					71		70		69					
	80					76		75		74					
	90							85		84					
100								95		94					
	110							105		104					<del></del>
	120							115		114	00				<del></del>
	130			Lyna	<u>l</u> thout shar	k ribe	<u> </u>				80 80				
	140 150			LV WI	u iout snar	IK FIDS	T				80				
150 160											80				$\vdash$
	180										80				$\vdash$
	190										80				
	200										80				

Other screw lengths with  $L_{min} \leq L \leq L_{max}$  and other thread lengths  $lg \geq 4*d$  up to max. standard thread length, are allowed


HECO-UNIX-plus and HECO-UNIX-top screws	
HECO-UNIX-plus Countersunk Head, Pozi-Drive, carbon steel	Annex 3.1



Nom.	Diameter	Ø	3,5	Ø	4,0		4,5	Ø	5,0	Ø					
d upper tol. lower tol.		3,5	+0,3 -0,1	4,0	+0,3 -0,1	4,5 +0,3 -0,1		5,0	+0,3 -0,1	6,0 +0,3 -0,1					
d <sub>1</sub>	upper tol. lower tol		35 15	2,6 2,4		2,9 2,7		3,2 3,0		4,2 3,8					
<i>d</i> h	upper tol. lower tol.	6,9	+0,1 -0,4	7,9	+0,1 -0,4	8,9 +0,1 -0,4		9,6	+0,1 -0,4	11,7	7 <sup>+0,1</sup> <sub>-0,4</sub>				
ds	upper tol. lower tol.										,5 ,3				
P		Variable thread pitch													
k	upper tol. lower tol.		,1 ,8		,5 ,1		,7 ,3	3,0 2,6		3,	,6 ,1				
R	ecess	HD/	T-15	HD/	T-20	HD/	T-20	HD/	T-25	HD/	T-30				
t	t upper tol. lower tol.		,6 ,3		55 25	1,55 1,25		2,25 1,85		2,5 2,1					
Α		3,35			3,94		3,94		53	5,63					
	L	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt
	20	16		16				15							
	25	21		21		21		20							
	30	26		26		26		25		24					
	35	31		31		31		30		29					
	40 45	36 41		36 41		36 41		35 40		34 39					-
	50	46		41		46		45		44					-
	55	40		51		51		50		49					$\vdash$
	60			56		56		55		54					$\vdash$
	65			61		61		60		59					
	70			66		66		65		64					
	75					71		70		69					
	80					76		75		74					
90								85		84					
100								95		94					<u> </u>
110								105		104					
120						-		115		114	90			-	<del>                                     </del>
	130 140			Lywi	<u>I</u> thout shar	k ribe			-		80 80				
	150			LVWI	Tiout snar	IK HDS					80				$\vdash$
	160										80				$\vdash$
	180				<del>                                     </del>	<del>                                     </del>					80				<b>—</b>
	190										80				
200											80				

Other screw lengths with  $L_{min} \leq L \leq L_{max}$  and other thread lengths  $lg \geq 4*d$  up to max. standard thread length, are allowed


HECO-UNIX-plus and HECO-UNIX-top screws	
HECO-UNIX-plus Countersunk Head, T-Drive, carbon steel	Annex 3.2



Nom.	diameter	Ø	3,5	Ø	4,0	Ø	4,5	Ø	5,0	Ø	6,0						
d upper tol. lower tol.		3,5	+0,3 -0,1	4,0	+0,3 -0,1	4,5	4,5 +0,3   5,0		+0,3 -0,1	6,0	6,0 <sup>+0,3</sup> <sub>-0,1</sub>						
<i>d</i> <sub>1</sub>	upper tol. lower tol.	2, 2,	35 15	2,65 2,45		2,9 2,7		3,2 3,0		4,1 3,8							
<i>d</i> h	upper tol. lower tol.	6,9	+0,1 -0,4	7,9	+0,1 -0,4			9,6	+0,1 -0,4	11,7	11,7 +0,1 -0,4						
<i>d</i> s	upper tol. lower tol.									4 4	,4 ,2						
Р							Va	riable th	nread p	itch							
k	upper tol. lower tol.		,1 ,8		,5 ,1		,7 ,3		,0 ,6	3	,6 ,1						
Re	ecess Z	1 :	2		2	1 2	2	1 2	2 3								
t upper tol. lower tol.		2,	15 ,7	2	,6 05	3,	15 65	3	,6 ,0	3,6 3,0		3,6					
	m		,0	_	,4				,3	6,6							
	L	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt		
	20	16															
	25	21		21				0.5									
	30	26		26		26		25									
	35 40	31 36	-	31 36	_	31 36	<u> </u>	30 35		35			_		-		
	45	41		41		41		40		40							
	50	46	1	46		46		45		45					<del>                                     </del>		
	55	70		51		51		50		50					-		
	60			56		56		55		55							
	65			61		61		60		60							
	70			66		66		65		65							
	75			71		71		70		65							
	80			76		76		75		65							
	90							85		85							
100								95		95							
	110			-				105		105					-		
120 130			_	_				115		115 125							
140			-	Lywi	<u>I</u> thout shar	ok ribe		-		135					-		
150				T LV WI	Tilout silai	I		<del>                                     </del>		145					$\vdash$		
160			<del>                                     </del>							155					$\vdash$		
180			1							1.00	80						
190											80						
200											80						
	220										80						
	240										80						
	260										80						
	280										80						
	300										80						

Other screw lengths with  $L_{min} \le L \le L_{max}$  and other thread lengths  $lg \ge 4*d$  up to max. standard thread length, are allowed

HECO-UNIX-plus and HECO-UNIX-top screws	
HECO-UNIX-top Countersunk Head, Pozi-Drive, carbon steel	Annex 3.3



Nom.	diameter		3,5	Ø	4,0		4,5	Ø	5,0	Ø	6,0						
d	d upper tol. lower tol. 3		+0,3 -0,1	4,0	+0,3 -0,1	4,5	+0,3 -0,1	5,0 <sup>+0,3</sup> <sub>-0,1</sub>		6,0 +0,3							
<i>d</i> <sub>1</sub>	upper tol. lower tol.	2, 2,	35 15	2,65 2,45		2,9 2,7		3,2 3,0		4,1 3,8							
<i>d</i> h	upper tol. lower tol.	6,9	6,9 <sup>+0,1</sup> <sub>-0,4</sub>		6,9 +0,1		+0,1 -0,4	8,9	+0,1 -0,4	9,6	+0,1 -0,4	11,7	7 +0,1 -0,4				
d <sub>s</sub>	upper tol. lower tol.											4	,4 ,2				
P							Va	riable th	read p	itch							
k	upper tol. lower tol.	2	,1 ,8		,5 ,1	2 2	,7 ,3		,0 ,6		,6 ,1						
R	ecess		T-15		T-20		T-25		T-25	HD/							
t	upper tol. lower tol.	1	,6 ,3	1,	55 25	1	,9 ,5	2,	25 85		,5						
	A		35		94	4,53		4,53 5,63		-							
	L	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt		
	20	16															
	25	21		21				0.5									
	30 35	26 31		26 31		26 31		25 30									
	40	36		36		36		35		35							
	45	41		41		41		40		40							
	50	46		46		46		45		45							
	55			51		51		50		50							
	60			56		56		55		55							
	65			61		61		60		60							
	70			66		66		65		65							
	75			71		71		70		65							
	90			76		76		75 85		65 85							
	100		_				_	95		95			_				
	110							105		105							
	120							115		115							
	130									125							
140				Lv wi	thout shar	nk ribs				135							
150										145							
	160									155							
180											80						
190											80						
	200										80						
	220										80						
240			-								80 80						
260 280			-				-				80						
	300										80						
	500										00						

Other screw lengths with  $L_{min} \le L \le L_{max}$  and other thread lengths  $lg \ge 4*d$  up to max. standard thread length, are allowed


HECO-UNIX-plus and HECO-UNIX-top screws	
HECO-UNIX-top Countersunk Head, T-Drive, carbon steel	Annex 3.4

60

65 70

75





Other screw lengths with  $L_{min} \le L \le L_{max}$  and other thread lengths  $lg \ge 4*d$  up to max. standard thread length, are allowed

61

66

76


61

66

76

Lv without shank ribs


HECO-UNIX-plus and HECO-UNIX-top screws	
HECO-UNIX-top cladding screw with raised Countersunk Head, T-Drive, stainless steel	Annex 3.5




Nom.	diameter		3,5	Ø	4,0	Ø	4,5	Ø:	5,0	Ø	6,0				
d	upper tol. lower tol.	3,5	+0,3 -0,1	4,0	+0,3 -0,1	4,5	+0,3 -0,1								
<i>d</i> <sub>1</sub>	upper tol. lower tol.	2, 2,	35 15		65 45	2 2	,9 ,7								
<i>d</i> h	upper tol. lower tol.	5,2	+0,2 -0,2	6,1	+0,1 -0,3	6,8	+0,1 -0,3								
ds	upper tol. lower tol.														
Р	-						Va	riable th	read p	itch					
k	upper tol. lower tol.			3 2	,1 ,7	3	,4 ,0								
R	ecess	HD/T-10		HD/T-15		HD/	D/T-20								
t	upper tol. lower tol.	1 1,	,5 25		65 ,4		55 25								
	Α	3,	35	3,	94	4,	53								
	L	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt	Lv	Lt
	20 25 30														
	35 40	36		36											
	45	41		41											
	50 55	46 51		46 51		45 50									
	60	56		56		55									
	65			61		60									
	70			66		65									
75 80						70 75									
			Lv wi	thout shar	k ribs	,,,									

Other screw lengths with  $L_{min} \leq L \leq L_{max}$  and other thread lengths  $lg \geq 4*d$  up to max. standard thread length, are allowed

HECO-UNIX-plus and HECO-UNIX-top screws	
HECO-UNIX-top Floorboard screw with raised Countersunk Head, T-Drive, carbon steel	Annex 3.6



Cylinde	Cylinder head										
Nom. diameter	d <sub>h</sub>	+Tol -Tol	k	+Tol	HD/T- Drive	t +Tol -Tol	А	PZ-Drive	t +Tol -Tol	m	
3,5	6,5	+0		2,7	HD/T-15	1,85	3,35	2	1,85	2.0	
3,5	0,3	-0,4		2,3	ПD/1-13	1,6			1,6	3,8	
4,0	7,0	+0,2		2,9	HD/T-20	2,0	3,94	2	2,46	4,4	
4,0	7,0	-0,2	2,5	2,5	110/1-20	1,6			2,2		
4,5	8,0	+0	3,7	HD/T-25	2,72	4,53	2	2,72	4,6		
4,5	0,0	-0,5		3,3	HD/1-23	2,26	4,55	2	2,26	4,0	
5.0	8,0	+0		3,7	UD/T 25	2,72	4.50	2	3,15	<i>E</i> 1	
5,0	0,0	-0,5		3,3	HD/T-25	2,26	4,53		2,59	5,1	
6,0	9,0	+0,3		4,2	HD/T-30	3,0	5,63	3	3,48	6,7	
	9,0	-0,3		3,8	HD/1-30	2,5	5,05	3	3,02		



Pan	head						Recess					
Nom. diameter	d <sub>h</sub>	+Tol	k	+Tol	T-Drive	t +Tol	А	PZ-Drive	t +Tol -Tol	m		
3,5	7,0	+0		2,6 HD/T-15	1,85	3,35	2	1,85	2.0			
3,5	7,0	-0,4	2	2,35	HD/1-13	1,6	3,33		1,6	3,8		
4,0	8,0	+0		2,9	HD/T-20	2,0	3,94	2	2,46	4,4		
4,0	0,0	-0,5	2	2,55	110/1-20	1,6	3,94		2,2	7,7		
4,5	9,0	+0	3	3,05	HD/T-25	2,72	4,53	2	2,72	4,6		
4,5	9,0	-0,5	2	2,75	HD/1-23	2,26	4,55		2,26	4,0		
5,0	9,7	+0	0.7 +0		3,4	HD/T-25	2,72	4,53	2	3,15	5,1	
5,0	9,1	-0,5		3,1	ПБ/ 1-25	2,26	4,55		2,59	5,1		
6,0	11,8	+0		4,0	HD/T-30	3,5	5,63	3	3,48	6.7		
0,0	11,0	-0,6		3,7	110/1-30	2,8	3,03		3,02	6,7		

HECO-UNIX-plus and HECO-UNIX-top screws	
HECO-UNIX Head-Types, carbon steel / stainless steel	Annex 3.7





#### **HECO-Schrauben GmbH & Co.KG**

Dr.-Kurt-Steim-Straße 28 · D-78713 Schramberg
Tel.: +49 (0) 74 22 / 9 89-0 · Fax: +49 (0) 74 22 / 9 89-200
Mail: info@heco-schrauben.de · www.heco-schrauben.com